

Fercell manufacture a range of fully enclosed spray rooms and heated drying rooms to customers' specific requirements. These are designed by engineers with both practical and managerial experience in the product finishing field.

All Fercell spray rooms are free-standing and of a modular construction. The units include an integrated filtered extraction system - either a Fercell Sirocco Dry-Back or a Fercell Cascade Water-Wash system. There is also the option of a gas, LPG or electrically heated filtered air input system within the drying room.

Spray rooms can be incorporated into the structure of existing buildings or combined with a heated drying room or a Fercell drying oven.

The Fercell modular system of room construction can be adapted readily to convert an existing spray booth to a spray/drying room.



Due to the continued improvement of our products, specifications may vary from those provided in this leaflet. We reserve the right to alter specifications and dimensions without prior notice. Any non standard sizes manufactured to specific requirements. All dimensions quoted are approximate.